

Six steps to safe maintenance

Stay safe, lock off and prove dead with Martindale VIPDLOK kits



Disconnect all loads.



Locate the source of supply.



Isolate the source of supply. Lock off and place warning signs.



Prove your voltage indicator using a proving unit.



Test the supply is isolated.



Martindale VIPDLOK Kits, complete solutions for safe isolation and Electricity at Work compliance.

Re-prove the voltage indicator using a proving unit.



www.martindale-electric.co.uk

Call: 01923 441717 email: sales@martindale-electric.co.uk

MARTINDALE
ELECTRIC
Keeping You Safe